



PROJECT ESTIMATE

Front Yard Renovation

Concrete Pads, Turf, Steps, Block Wall & Lighting

PREPARED FOR

Brian Stampley

40206 Holden Circle
Temecula, California 92591
(805) 300-3413

ARIEL OUTDOOR RENOVATION

Class B General Building Contractor · Specializing in outdoor renovation

940 SF CONCRETE PADS · 870 SF ARTIFICIAL TURF · 75 LF BLOCK WALL · LED LIGHTING

DATE

June 17, 2026

ESTIMATE NO.

AOR-061726-S001

VALID FOR

30 Days

01 · SCOPE OF WORK

What We're Building

Your full front yard renovation, built start to finish by our own crews. Here is everything included in the project.

- 1

Driveway: Concrete Pads with Turf Joints

Concrete pads in a grid pattern, about 4 ft by 4 ft each, with 3 inch artificial turf strips between every pad. Includes demo of the existing surface, base prep and compaction, forming and pouring the pads, and setting the turf strips.

840 sf
- 2

Side Area Near House

Grade and level the area, then install concrete pads with turf strips in the same grid style as the driveway.

100 sf
- 3

Main Staircase

About 5 ft wide with a 7 ft run, finished with recessed warm white LED strip lighting under each step.

3 steps
- 4

Second Staircase Area

Two to three steps, about 7 ft long, with under step LED step lighting.

~16 ft
- 5

Block Wall

White smooth stucco finish for a modern look, with provisions for lights and planting pockets. Includes footing, block, grout, finish, and cap.

75 lf x 4 ft
- 6

Artificial Turf Area

Grade and level, plate compact the base, weed barrier, then install artificial turf with infill and edging.

870 sf
- 7

Tree Removal

Remove 3 palm trees (1 large and 2 medium), pull the stumps, and haul away all debris.

3 palms
- 8

Landscape Lighting (Low Voltage)

Under step LED strips on both staircases, path lights, and wall lights, with transformer, wiring, and full hookup.

throughout
- 9

Planting Prep

Prepare planting pockets and areas along the block wall and walkways.

included
- 10

Demo & Disposal

Demo of all existing surfaces and haul away of all debris.

included