



PROJECT ESTIMATE

Front Yard Renovation

Concrete Pads, Turf, Steps, Block Wall & Lighting

PREPARED FOR

Brian Stampley

40206 Holden Circle
Temecula, California 92591
(805) 300-3413

ARIEL OUTDOOR RENOVATION

Class B General Building Contractor · Specializing in outdoor renovation

940 SF CONCRETE PADS · 870 SF ARTIFICIAL TURF · 75 LF BLOCK WALL · LED LIGHTING

DATE

June 17, 2026

ESTIMATE NO.

AOR-061726-S001

VALID FOR

30 Days

01 · SCOPE OF WORK

What We're Building

Your full front yard renovation, built start to finish by our own crews. Here is everything included in the project.

- 1

Driveway: Concrete Pads with Turf Joints

Concrete pads in a grid pattern, about 4 ft by 4 ft each, with 3 inch artificial turf strips between every pad. Includes demo of the existing surface, base prep and compaction, forming and pouring the pads, and setting the turf strips.

840 sf
- 2

Side Area Near House

Grade and level the area, then install concrete pads with turf strips in the same grid style as the driveway.

100 sf
- 3

Main Staircase

About 5 ft wide with a 7 ft run, finished with recessed warm white LED strip lighting under each step.

3 steps
- 4

Second Staircase Area

Two to three steps, about 7 ft long, with under step LED step lighting.

~16 ft
- 5

Block Wall

White smooth stucco finish for a modern look, with provisions for lights and planting pockets. Includes footing, block, grout, finish, and cap.

75 lf x 4 ft
- 6

Artificial Turf Area

Grade and level, plate compact the base, weed barrier, then install artificial turf with infill and edging.

870 sf
- 7

Tree Removal

Remove 3 palm trees (1 large and 2 medium), pull the stumps, and haul away all debris.

3 palms
- 8

Landscape Lighting (Low Voltage)

Under step LED strips on both staircases, path lights, and wall lights, with transformer, wiring, and full hookup.

throughout
- 9

Planting Prep

Prepare planting pockets and areas along the block wall and walkways.

included
- 10

Demo & Disposal

Demo of all existing surfaces and haul away of all debris.

included

02 · INVESTMENT

Investment & Timeline

Hi Brian,

Below is the turnkey price for your full front yard renovation. It covers labor, materials, equipment, and on-site management for everything in the scope.

940 sf

Concrete Pads

870 sf

Artificial Turf

\$73,800

Total Investment

WHAT'S INCLUDED

- All labor, materials, and equipment.
- Demo and haul-off of the existing surfaces.
- Concrete pads with turf joints (driveway and side area).
- 870 sf artificial turf area.
- Two LED-lit staircases.
- 75 lf white block wall, footing to cap.
- Removal of 3 palm trees and stumps.
- Low voltage landscape lighting and planting prep.

MATERIALS & SELECTIONS

Concrete Pads

Poured concrete pads in a 4 ft grid with 3 inch artificial turf joints.

Artificial Turf

Premium landscape grade synthetic turf, supplied and installed.

Block Wall

75 lf, 4 ft high, white smooth stucco finish, footing to cap.

Lighting

Low voltage warm white LED: under step strips, path lights, and wall lights.

TOTAL PROJECT INVESTMENT

Turnkey: labor, materials, equipment & management included.

\$73,800

TIMELINE About 3 weeks from start to final walkthrough, weather permitting.

PAYMENT SCHEDULE · PER CALIFORNIA CSLB RULES

Down payment limited to \$1,000 by law. Progress payments tied to on-site milestones.

#	MILESTONE	AMOUNT	%
1	Contract signing (down payment, CA cap \$1,000)	\$1,000	1.4%
2	Upon material delivery	\$35,000	47.4%
3	Upon demo & excavation	\$20,000	27.1%
4	Upon base & block wall completion	\$16,800	22.7%
5	Completion & final walkthrough	\$1,000	1.4%
TOTAL		\$73,800	100%

NOT INCLUDED

Permits beyond the block wall · HOA fees · drainage / utility relocation · furniture & accessories · any work outside this scope.

Questions? Call Jacob Hayon, Project Manager directly at (323) 513-4865 anytime.

Accepted by (client signature)

Date

This is an estimate, not a contract. Pricing valid 30 days from the cover date. A formal California home-improvement contract supersedes this document upon signing.